



NOTES:

1. CONNECTION TO SEWER MAIN PER STANDARD DWG S-9.
2. INSTALL 6" MINIMUM PIPE SIZE IN RIGHT OF WAY.
3. INSTALL 6" CLEANOUT PER STANDARD DWG S-10.
4. PRIVATE SIDE SEWER PIPE DIAMETER:
4" MINIMUM FOR SINGLE FAMILY
6" MINIMUM FOR OTHER USES
5. ALL CLEANOUTS ON PRIVATE PROPERTY ARE TO BE ADJUSTED TO GRADE PER STANDARD DWG S-9.
6. CLEANOUTS ARE TO BE CONSTRUCTED WITH WYES. STRAIGHT "T'S ARE NOT PERMITTED.
7. ALLOWABLE GRADES ARE 2% (1/4"FT) MINIMUM TO 100% (FT/FT) MAXIMUM.
8. SEWER MUST BE STRAIGHT BETWEEN ANGLE POINTS, CHANGES IN LINE OR GRADE SHALL BE MADE WITH APPROVED FITTINGS.
9. NORMALLY ONLY ONE(1) CONNECTION TO THE SEWER MAIN PER BLDG. IS ALLOWED. TWO (2) DIFFERENT LAYOUTS ARE SHOWN FOR ILLUSTRATIVE PURPOSES ONLY.

NO SCALE



APPROVAL

Wayne R. Haafle

PUBLIC WORKS DIRECTOR

DATE
01/21/2022

DRAWING NO.

S-7

REV:

**TYPICAL SIDE SEWER
LAYOUT**