



NOTES:

1. 2"X4" PRESSURE TREATED WOOD SERVICE MARKER, LENGTH AS REQUIRED. PAINT PORTION OF SERVICE MARKER THAT IS ABOVE GRADE WITH WHITE PAINT. STENCIL "S/S" WITH 3" TALL BLACK LETTERS.
2. FOR NEW SEWER MAINS, INSTALL A MANUFACTURED WYE WITH 45° BEND WITH THE MAIN LINE CONSTRUCTION. FOR EXISTING SEWER MAINS, CORE DRILL AND INSTALL A INSERT-WYE SADDLE.
3. APPROVED WATERTIGHT CAP PLUG OR CONTINUE PIPE.
4. PROVIDE DETECTOR TAPE 12" OVER BEDDING FOR ENTIRE LENGTH OF STUB AND UP 2"X4" SERVICE MARKER.
5. FOR DEVELOPER EXTENSION PROJECTS, EXTEND STUB 10' INTO PROPERTY; OTHERWISE, TERMINATE STUB AT PROPERTY LINE OR EDGE OF EASEMENT.
6. 6" SIDE SEWER STUB AT 2% MINIMUM SLOPE, 100% (45°) MAXIMUM SLOPE.

NO SCALE



APPROVAL

Wayne R. Haufe

PUBLIC WORKS DIRECTOR

**SIDE SEWER STUB
CONNECTION TO
EXISTING OR NEW MAIN**

DATE
01/21/2022

DRAWING NO.

S-9

REV: