



STREET GENERAL NOTES:

1. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO PROVIDE ADEQUATE TEMPORARY TRAFFIC CONTROL TO ENSURE TRAFFIC SAFETY DURING CONSTRUCTION ACTIVITIES. THE CONTRACTOR SHALL SUBMIT A TRAFFIC CONTROL PLAN TO THE TOWN AT LEAST FIVE BUSINESS DAYS PRIOR TO STARTING ANY WORK IN THE RIGHT-OF-WAY. ALL TRAFFIC CONTROL DEVICES SHALL CONFORM TO THE "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES" (MUTCD).
2. ALL CURB AND GUTTER, STREETS, SIDEWALKS, AND ANY OTHER HORIZONTAL CONSTRUCTION SHALL BE STAKED BY AN ENGINEERING FIRM, SURVEYING FIRM, OR TOWN AUTHORIZED CONTRACTOR CAPABLE OF PERFORMING SUCH WORK.
3. THE SUBGRADE AND CRUSHED SURFACING MATERIAL SHALL BE COMPACTED TO 95% MAXIMUM DENSITY. HMA SHALL BE COMPACTED TO 92% MAXIMUM DENSITY.
4. FORM AND SUBGRADE INSPECTION BY THE TOWN IS REQUIRED BEFORE PLACING CONCRETE CURB AND GUTTER AND SIDEWALK. TWO BUSINESS DAYS NOTICE IS REQUIRED FOR FORM INSPECTION.
5. SIDEWALK AND CURB AND GUTTER MAY NOT BE POURED MONOLITHICALLY. THERE MUST BE A COLD JOINT OR FULL-DEPTH EXPANSION JOINT BETWEEN THEM.
6. WHERE NEW ASPHALT JOINS EXISTING, THE EXISTING ASPHALT SHALL BE CUT TO A NEAT VERTICAL EDGE AND TACKED WITH SEALER. SEALANT SHALL MEET THE REQUIREMENTS OF ASTM D6690 TYPE OR TYPE 11.
7. IN THE CASE OF NEW ROAD CONSTRUCTION OR RECONSTRUCTION REQUIRING MAILBOXES TO BE MOVED OR REARRANGED, THE APPLICANT/CONTRACTOR SHALL COORDINATE WITH THE U.S. POSTAL SERVICE FOR THE NEW LOCATION OF THE MAILBOX STRUCTURE(S).
8. ANY EXISTING PUBLIC IMPROVEMENTS DAMAGED DURING CONSTRUCTION SHALL BE REPLACED PRIOR TO FINAL INSPECTION.
9. ANY WORK INVOLVING UTILITY EQUIPMENT SHALL BE IN ACCORDANCE WITH THE UTILITY COMPANY.
10. ANY JUNCTION BOXES AND VAULTS SHALL LOCATED IN A SIDEWALK SHALL HAVE SLIP RESISTANT LIDS AND FRAMES.
11. JUNCTION BOXES AND VAULTS SHALL NOT BE LOCATED WITHIN A SIDEWALK RAMP OR DRIVEWAY ENVELOPE.
12. ALL ILLUMINATION CONDUIT SHALL BE SCHEDULE 80 PVC.
13. ALL LIGHT STANDARDS SHALL BE HAPCO MODEL RTA25D7BM16-01. LUMINAIRE SHALL BE CREE MODEL BXSP_BP_HT_3ME_40K_UL_SV_N_Q9.

NO SCALE

	APPROVAL  PUBLIC WORKS DIRECTOR	
	DATE 01/21/2022	DRAWING NO. ST-0
STREET GENERAL NOTES		REV: