



NOTES:

1. TREE SHALL BE 2" CALIBER MEASURED 6" ABOVE THE CROWN. TREE SHALL BE IN GOOD HEALTH AND FORM AND CONFORM TO WSDA STANDARDS. SPECIES SHALL BE ON TOWN'S TREE LIST.
2. PLACE ROOT BARRIER AT EDGE OF PAVEMENT/SIDEWALK PRIOR TO PLACEMENT OF SIDEWALK OR CURB & GUTTER TO PREVENT UNDERMINING.
3. "CHAINLOCK" OR EQUAL TREE TIE MATERIAL (1" SIZE) NAIL OR STABLE TREE TIE MATERIAL TO STAKE TO HOLD VERTICALLY LOOP EACH TIE AROUND HALF TREE LOOSELY TO PROVIDE 1" SLACK FOR TRUNK GROWTH.
4. TREES SHALL BE HANDLED TO ENSURE PROTECTION AND FULL SUPPORT UNDER THE ROOT BALL AND ORIENTED TO ALIGN STRUCTURAL BRANCHES FOR OPTIMUM COMPATIBILITY WITH BUILDINGS AND ADJACENT STREET/SIDEWALK CLEARANCES. REMOVE TWINE, BURLAP AND WIRE BASKETS TO EXPOSE THE TOP 2/3 OF THE ROOT BALL. ALL OTHER CONTAINERS, GROW BAGS AND MATERIALS USED IN THE COMMERCIAL PRODUCTION OF NURSERY STOCK SHALL BE REMOVED ENTIRELY FROM THE ROOT BALL. ROOTS SHOULD BE PRUNED, LOOSEND AND/OR STRAIGHTENED TO ENSURE PROPER GROWTH AND ESTABLISHMENT.
5. INSTALL TREE GATOR SLOW RELEASE WATERING BAG OR EQUAL ON EACH TREE. CONTRACTOR SHALL FILL BAGS A MINIMUM OF TWO TIMES PER WEEK UNTIL TOWN ACCEPTS PROJECT.
6. TOPSOIL SHALL BE 10% COMPOST AND 90% SANDY LOAM BY VOLUME, AND SCREENED THROUGH 3/8" SCREEN.
7. SHAPE SOIL SURFACE TO PROVIDE 4' DIAMETER WATERING RING 3" TO 4" HIGH.
8. A TOWN REPRESENTATIVE SHALL BE PRESENT DURING TREE PLANTING. TWO BUSINESS DAY NOTICE IS REQUIRED.

NO SCALE



APPROVAL

PUBLIC WORKS DIRECTOR

DATE 01/21/2022	DRAWING NO. ST-28	REV:	TREE PLANTING